

site plan scale 1" = 20'-0"



this site plan is diagrammatical. not to be construed as actual survey. actual conditions and dimensions may vary, verify and confirm the accuracy of this site plan prior to commencement

(for architectural review use)

ediger residence

3300 thomson circle, rocky river, ohio

code summary & design criteria

2019 residential code of ohio 2023 national electric code 2018 international energy conservation code

Design Snow Load: section 301 design criteria figure 301.2(5) ground snow loads roof snow load = 30 psf

Design Wind Load: table 301.2(2) component and cladding loads for a building with a mean roof height of 30 feet located in exposure b 115 mph (V_{uh}) (3 second gust)

baseline structural criteria & design information

Framing Lumber (Minimum): E = 1,400,000 psi Fb = 875 psi Fv = 135 psi

Microlam (LVL): E = 2,000,000 psi Fb = 2800 psi Fv = 285 psi

Steel: ASTM A-36 E = 29,000,000 psi Fy = 36 ksi Fy = 14,5 ksi W Shapes: Fy= 50,000 psi (astm A992) Pipes: Fy= 46,000 psi (astm A500 Grade B) Plates: Fy= 36,000 psi (astm A36) Anchor Boths: Astm A307 (may Use A36 or A325)

Live Loads: Roof = 30 psf Floor = 40 psf Soil Bearing Capacity (Min.): 1500 psf Floor = 40 psf Floor 30 psf (sleeping) Ceilings = 20 psf Attic = 30 psf Decks = 40 psf Balconies (Exterior) = 40 psf

Allowable Deflection:
Rafters = L/240
Ceilings = L/360
Floors = L/480
Floors with tile = L/600
Beams & Headers = L/480
Lintels ex Macans = L/600 Lintels for Masonry= 1/600 (L = Span Length) Truss Data (Min.):
Top Chord: LL= 30 psf
DL= 15 psf
Bottom Chord: LL= 10 psf
DL= 10 psf

Dead Loads: Roof = 15 psf Ceilings = 10 psf Floor = 10 psf Concrete:
Footings: Fc= 3000 psi,
Slabs: Fc- 4000 psi
(with 6% Air Entrainment
For Exterior Exposure) Seismic Category A or B

Concrete Block:

F'm= 1500 psi

Wind Speed (design) 115 mph (Vult) (3 second gust)

color & finish schedule

	Type	Color
Siding Roof		
Roof		
Brick		
Stone		
Trim		
Shutters		
Soffit		

structural notes

- 1. The structural specifications are a suggested baseline and should be verified prior to the commencement of construction. The building contractor should adjust these values as required to meet
- 2. The drawings show the general details of construction. The contractor shall notify the designer where additional details are required, or where conditions are encountered that are not anticipated by
- 3. The contractor is to verify all dimensions prior to fabrication and construction. Notify designer of any discrepancies.
- 4. The structure is designed to be self-supporting and stable after the building is fully completed. it is the contractor's sole responsibility to determine erection procedure and sequence and ensure the safety of the building and its component parts during construction. This includes the addition of whatever shoring, temporary bracing, underpinning, earth retention, etc. that may be necessary.

square footage data (square feet)

upper floor addition 376

huilding information

Building Location:

A complete and careful review of these plans should be performed by the party responsible for executing the work prior to construction

The building contractor should verify all site conditions and review all manufacturer's shop drawings for compliance prior to assembly, installation or construction

All framing and structural elements must comply with all governing codes and be installed according to common practice and industry standards.

All federal, state and local codes, ordinances and regulations, etc. shall be considered a part of the specifications of this building; and are to be adhered to even if they are in variance with the

nananiy mioi mation	(building department use)
Owner's Name:	
Builder's Name:	
Builder's Phone:	

sheet 1 cover sheet sheet 2 elevations sheet 3 elevations sheet 4 main floor plan sheet 5 upper floor plan sheet 6 sections sheet 7 details sheet 8 electronech plans

Copyright 2025 Bennett Builden

All rights reserved. This design and these plans or part thereof must not be re-produced in any form without the written permission of Bennett Builders. These plans can only be used for the specific orgical stated in the







ohio rocky river, The second of 3 circle, ediger

issued: 04/02/25
first draft
progress
design review
bid-estimates
approval
permit

front elevation





right side elevation

scale 1/4" = 1'-0"

sheet 1 cover sheet sheet 2 elevations sheet 3 elevations sheet 4 main floor plan sheet 5 upper floor plan sheet 6 sections sheet 7 cetails sheet 8 elec-mech. plans

Copyright 2025 Bennett Builders





Issued: 04/02/25
If itst draft
Progress
design review
bid-estimates
approval
permit
not for construction
revised: 04/03/25

left side elevation

scale 1/4" = 1'-0"





Issued: 04/02/25
Institution

general plan notes

2) BUILDING CONTRACTOR MUST VERIFY ALL SITE CONDITIONS PRIOR TO COMMENCEMENT OF CONSTRUCTION.

3) ALL WALL ANGLES ARE 45 DEGREES UNLESS OTHERWISE NOTED.

4) FIELD VERIFY ALL WINDOW LOCATIONS & ROUGH OPENINGS AS REQUIRED WITH WINDOW MANUFACTURERS SPECIFICATIONS. 5) PROVIDE SAFETY GLASS FOR WINDOW GLAZING < 18" A.F.F. OR ADJUST WINDOW SIZE TYP.

6) STRUCTURAL AND FRAMING MEMBERS INDICATED ARE SIZED BASED ON SPECIES OF LUMBER THAT SATISFY THE SPAN.

7) BUILDER TO VERIFY THAT ALL CEILING JOISTS AND RAFTER BRACINGS BEAR ON LOAD BEARING WALLS WHICH ALIGN AS SHOWN AND TERMINATE AT FOUNDATION AND BE SUPPORTED THICKENED SLAB GRADE BEAM OR FOOTING AS INDICATED.

8 JUNLESS NOTED OTHERWISE- ALL NON-STRUCTURAL RIDGE BOARDS TO BE (1)2X12 MIN. ALL HIP RAFFERS TO BE (1)2X12 MIN. ALL HIP RAFFERS TO BE (1)2X12 MIN. POWOIDE POST UP SUPPORTS FROM SOUND BEARINGS OR TRIPLE CEILING JOISTS MINIMUM.

floor joist schedule

J1 2X10 floor joists @ 16" o.c. with 'x' bracing @ midspan or as required.

J2 2X10 floor joists @ 12' o.c. with 'x' bracing @ midspan or as required.

J3 2X10 floor joists @ 16' o.c. double every other joist with 'x' bracing @ midspan or as required.

(2) 2X10 floor joists @ 16" o.c. with 'x' bracing @ midspan or as required.

J5 2X10 treated floor joists @ 16" o.c. with bracing @ midspan or as required.


J6 2X8 treated floor joists @ 16" o.c. with bracing @ midspan or as required.

J7 2X12 floor joists @ 16" o.c. with 'x' bracing @ midspan or as required.

J8 2X12 floor joists @ 12" o.c. with 'x' bracing @ midspan or as required.

J9 2X12 floor joists @ 16" o.c. double every other joist with 'x' bracing @ midspan or as required.

(2) 2X12 floor joists @ 16" o.c. with 'x' bracing @ midspan or as required.



shear wall schedule

ALL EXTERIOR WALLS SHALL HAVE CONTINUOUS APA SHEATHING 32/16 1/2 OR 15/32 EXPOSURE 1 WITH SO COMMON NAILS AT 6 O.C. AT EDGES AND 1/2 O.C. AT INTERPREDIATE SUPPORTS WITH VETERIOR SHEWLY, IRVISIOL FOWERING OF 1/2* WINMON GYPSUM BOARD WITH 1 1/2* GALYANZED ROOFING NAILS, 1-1/2 LONG TAYLES GALYANZED. OR 1-1/4* LONG 1-1/4* UN OR 5 SCREWS AT 7: O.C. AT INTERPREDIATE SUPPORTS.

WALL TYPE 2 - TYPICAL INTERIOR SHEAR WALL CONSTRUCTION REQUIREMENTS

INTERIOR SHEAR WALLS AS INDICATED ON PLAN SHALL HAVE 1/2 GYPSUM BOARD WITH 50 X 1.56° GALVANZED NALS, OR NO. 6 X 1.16° LONG TYPE W. OR S.SCREWS A1 °C.O. A. I EDGES AND 1/2 O. C. A. II THE THE PLANT E SUPPORTION OR 55° GYPSUM BOARD WITH 60 X 1.78° GALVANIZED MALS OR NO. 6 X 1.14° LONG TYPE W. OR S. SCREWS AT 4′ O.C. AT EDGES AND 1/2 °C. AT INTERNEDIATE SUPPORTS

post & column schedule

P1 4x4 or (3)2x4 P6 3 1/2" x 5 1/4" PSL

P2 (4)2x4 P7 3 1/2" x 7" PSL

PB 5 1/4" x 5 1/4" PSL

P4 6x6 or (4) 2x6 P9 5 1/4" x 7" PSL

(P5) 3 1/2" x 3 1/2" PSL (P10) 3" dia. 11 ga. steel column with 1/2" bearing plate bolked to sound bearing

unless otherwise noted: all bearings to have a minimum of (1) jack stud per ply of header, built up beam or girder truss all posts in walls to be latterally braced full length all posts to continue down to sound foundation or solid bearing on structure below

all columns (posts) to have "simpson" post cap and base connectors

wood beam schedule

all wood framed h B1) (2) 2X10's (3) 1 3/4" X 11 7/8" LVL'S (2) 1 3/4" x 14" LVL's (3) 2x10's B3 (2) 1 3/4" x 9 1/4" LVL's B12 (3) 1 3/4" x 14" LVL's (3) 1 3/4" x 9 1/4" LVL's (2) 1 3/4" x 16" LVL's (3) 1 3/4" x 16" LVL's (B5) (2) 2x12's (3) 2x12's (2) 1 3/4" x 18" LVL's B7) (2) 1 3/4" x 11 1/4" LVL's (B19) (3) 1 3/4" x 18" LVL's (3) 1 3/4" x 11 1/4" LVL's (917) (2) 1 3/4" x 20" LVL's (2) 1 3/4" X 11 7/8" LVL'S (B19) (3) 1 3/4" x 20" LVL'S

p.t. - preservative treated GT girder truss (verify with mfg.)

w.p. - weather protected **2** xx indicates a doubled structural member

BENNETT BUILDERS & REMODELERS

sheef 1 cover sheet sheef 2 elevations sheef 3 elevations sheef 4 main floor plan sheef 5 upper floor plan sheef 5 exctons sheef 7 details sheef 8 elec-mech, plans

Copyright 2025 Bennett Builders All rights reserved. This design and these plans or part thereof must not be re-produced in any form without the written permission of Bennett Builders. These plans can only be used for the specific project stated in the trile block.



circle, rocky river, ohio 6 edigen

first draft
progress
design review
bid-estimates

approval
permit
not for construction
revised: 04/09/25

0376

general plan notes

2) BUILDING CONTRACTOR MUST VERIFY ALL SITE CONDITIONS PRIOR TO COMMENCEMENT OF CONSTRUCTION.

3) ALL WALL ANGLES ARE 45 DEGREES UNLESS OTHERWISE NOTED.

4) FIELD VERIFY ALL WINDOW LOCATIONS & ROUGH OPENINGS AS REQUIRED WITH WINDOW MANUFACTURERS SPECIFICATIONS.

5) PROVIDE SAFETY GLASS FOR WINDOW GLAZING < 18 $^{\circ}$ A.F.F. OR ADJUST WINDOW SIZE TYP.

6) STRUCTURAL AND FRAMING MEMBERS INDICATED ARE SIZED BASED ON SPECIES OF LUMBER THAT SATISFY THE SPAN.

7) BUILDER TO VERIFY THAT ALL CEILING JOISTS AND RAFTER BRACINGS BEAR ON LOAD BEARING WALLS WHICH ALIGN AS SHOWN AND TERMINATE A FOUNDATION AND BE SUPPORTED BY THICKENED SLAB GRADE BEAW OR FOOTING AS INDICATED.

BIUNLESS NOTED OTHERWISE- ALL NON-STRUCTURAL RIDGE BOARDS TO BE (1)2X12 MIN. ALL HIP RAFTERS TO BE (1)2X12 MIN. ALL VALLEY RAFTERS TO BE (2)2X12 MIN. PROVIDE POST UP SUPPORTS FROM SOUND BEARINGS OR TRIPLE CEILING JOISTS MINIMUM.

10) TREATED WOOD NOTICE: ALL ANCHORS. CONNECTORS. FASTEMERS ETC. MUST BE OF SUITABLE MATERIAL OF RESIST REACTION. OR CORROSION WITH THE TREATED LUMBER. CONSULT WITH MANUFACTURER OR MATERIAL SUPPLIER FOR PROPER FASTEMERS REQUIRED.

rafter/ceiling joist schedule

unless noted otherwise - Ceiling Joists at R1 2X10 rafters @ 16" o.c.

R2 2X8 rafters @ 16" o.c. R3 2X6 rafters @ 16" o.c.

R4 2X12 rafters @ 16" o.c.

C1 2X12 ceiling joists @ 16" o.c.

C2 2X10 ceiling joists @ 16" o.c. seclect structural

C3 2X10 ceiling joists @ 16" o.c.

C4 2X8 ceiling joists @ 16" o.c.


C5 2X6 ceiling joists @ 16" o.c.

T1 pre-engineered roof truss system refer to mfg. shop drawings

T2 pre-engineered roof truss system attic type refer to mfg. shop drawings

pre-engineered roof truss system scissor type OR modified refer to mfg, shop drawings

hatched area indicates 2x over framing-shore supporting rafters as req'd, typ.



shear wall schedule

WALL TYPE 1 - TYPICAL EXTERIOR SHEAR WALL CONSTRUCTION REQUIREMENTS

ALL EXTERIOR WALLS SHALL HAVE CONTINUOUS APA SHEATHING 32/16 (12° OR 1532° EXPOSURE 1 WITH-RO COMMON NAILS A 16° O.C. AT EDGES AND 12° O.C. AT INTERVENOEMES SUPPORTS WITH WITHEROO DRIVING. HIGHS COMPRISED OF 12° MINIMUM GYPSLIV BOARD WITH 112° CALVANZED ROCENIC NAILS, 1.12° LONG STAPLES CALVANZED, OR 1.14° LONG STAPLES CALVANZED, OR 1.16° LONG TYPE W ORS SCREWS AT 7° O.C. AT INTERMEDIATE SUPPORTS

WALL TYPE 2 - TYPICAL INTERIOR SHEAR WALL CONSTRUCTION REQUIREMENTS

WALL TYPE 2 - TYPICAL INTERIOR SHEAR WALL CONSTRUCTION REQUIREMENT INTERIOR SHEAR WALLS AS INDICATED ON PLAN SHALL HAVE 1/2" GYPSJUM BOARD WITH 50 X 1 56" GALVAN/ZED ANLS OR NO 6 X 1 1/4" LONG TYPE WOOD OR S SCREWS AT "0 CO. A TEDES AND 12" CO. A TIPE-MEMDIATE SUPPORTS OR 36" GYPSJUM BOARD WITH 60 X 1 1/8" GALVAN/ZED INAILS OR NO. 6 X 1 1/4" LONG TYPE WO RS SCREWS AT 4" O.C. AT EDGES AND 12" D.C. AT INTERMEDIATE SUPPORTS

post & column schedule

P1 4x4 or (3)2x4 P6 3 1/2" x 5 1/4" PSL

P7 3 1/2" x 7" PSL

P3 (3)2x6

P8 5 1/4" x 5 1/4" PSL

P4 6x6 or (4) 2x6 P9 5 1/4" x 7" PSL

(P5) 3 1/2" x 3 1/2" PSL (P10) 3" dia.11 ga. steel column with 1/2" bearing plate bolled to sound bearing

unless otherwise noted: all bearings to have a minimum of (1) jack stud per ply of header, built up beam or girder truss

all posts in walls to be latterally braced full length all posts to continue down to sound foundation or solid bearing on structure below

all columns (posts) to have "simpson" post cap and base connectors

wood beam schedule

all wood framed headers to be (2)2x10 min. unless noted otherwise

(B1) (2) 2X10's (B1) (3) 1 3/4" X 11 7/8" LVL'S (3) 1 3/4" X 11 7/8" LVL'S (2) 1 3/4" x 14" LVL's (3) 2x10's

B3 (2) 1 3/4" x 9 1/4" LVL's B12 (3) 1 3/4" x 14" LVL's B4 (3) 1 3/4" x 9 1/4" LVL's B13 (2) 1 3/4" x 16" LVL's B5 (2) 2x12's B12 (3) 1 3/4" x 16" LVL's

(3) 2x12's (2) 1 3/4" x 18" LVL's B7 (2) 1 3/4" x 11 1/4" LVL's B19 (3) 1 3/4" x 18" LVL's (3) 1 3/4" x 11 1/4" LVL's (B17) (2) 1 3/4" x 20" LVL's

(3) 1 3/4" X 11 7/8" LVL'S (3) 1 3/4" x 20" LVL's

p.t. - preservative treated GT girder truss (verify with mtg.) w.p. - weather protected 2xx indicates a doubled structural member

circle, rocky river, ohio 3 ediger

sheet 1 cover sheet sheet 2 elevations sheet 3 elevations sheet 4 main floor plan sheet 5 upper floor plan sheet 5 sections sheet 7 details sheet 8 electimeth, plans

Copyright 2025 Bennett Builders All rights reserved. This design and these plans or part thereof must not be re-produced in any form without the written permission of Bennett Builders. These plans can only be used for the specific project stated in the title block.

BENNETT BUILDERS & REMODELERS

issued: 04/02/25


first draft
progress
design review
bid-estimates
approval
permit
not for construction
revised: 04/09/25

0376

schematic roof diagram







typical upper wall section

scale 3/4" = 1'-0"






Issued: 04/02/25
If irst draft
Progress
design review
bid-estimates
approval
permit
not for construction
revised: 04/09/25



DETAILS FOR FULLY CONTINUOUS SHEATHING PER 2019 RESIDENTIAL CODE OF OHIO




RULES FOR DIMENSION "H"

- FOR "H" LESS THAN 9 1/4", NO BLOCKING REQUIRED
- FOR "H" GREATER THAN 9 1/4" UP TO 15 1/4". INSTALL BLOCKING PER ABOVE.
- FOR "H" GREATER THAN 15 1/4", FURTHER ENGINEERING IS REQUIRED.


EXTERIOR SHEAR WALL CONNECTION TO ROOF FRAMING

* NOTE: "SHEAR WALL" AND "BRACED WALL" TERMINOLOGIES ARE EQUAL AND INTERCHANGEABLE ON THIS DRAWING




EXTERIOR SHEAR WALL CONNECTION TO SILL PLATE ON FOUNDATION

1/2"=1'-0"




INTERIOR SHEAR WALL CONNECTIONS AT PARALLEL FLOOR/CEILING FRAMING

1/2"=1'-0"



INTERIOR SHEAR WALL CONNECTIONS AT PERPENDICULAR FLOOR/CEILING FRAMING



EXTERIOR SHEAR WALL CONNECTION AT FLOOR TO FLOOR FRAMING

1/2"=1'-0"

BRACED WALL CONSTRUCTION SPECIFICATIONS

WALL TYPE 1- TYPICAL EXTERIOR SHEAR WALL CONSTRUCTION REQUIREMENTS:

ALL EXTERIOR WALLS SHALL HAVE CONTINUOUS APA SHEATHING 32/16 1/2" OR 15/32" EXPOSURE 1 WITH 8D COMMON NAILS AT 6" O.C. AT EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS WITH INTERIOR DRYWALL FINISH COMPRISED OF 1/2" MINIMUM GYPSUM BOARD WITH 1 1/2" GALVANIZED ROOFING NAILS, 1 1/2" LONG STAPLES GALVANIZED, OR 1 1/4" LONG TYPE W OR S SCREWS AT 7" O.C. AT EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS

WALL TYPE 2 TYPICAL INTERIOR SHEAR WALL CONSTRUCTION REQUIREMENTS:

INTERIOR SHEAR WALLS AS INDICATED ON PLAN SHALL HAVE 1/2" GYPSUM BOARD WITH 5D X 1.5/8" GALVANIZED NAILS OR NO. 6 X 1.1/4" LONG TYPE W OR S SCREWS AT 4" O.C. AT EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS OR 5/8" GYPSUM BOARD WITH 6D X 1 7/8" GALVANIZED NAILS OR NO. 6 X 1 1/4" LONG TYPE W OR S SCREWS AT 4" O.C. AT EDGES AND 12" o.c. AT INTERMEDIATE SUPPORTS

DESIGN LOADING FOR BRACED WALLS:

DESIGN WIND COAD.

TABLE 301.2(2) COMPONENT AND CLADDING LOADS FOR A BUILDING WITH A MEAN ROOF HEIGHT OF 30 FEET LOCATED IN EXPOSURE B 115 MPH (VULT) (3 SECOND GUST)

sheet 1 cover sheet sheet 2 elevations sheet 3 elevations sheet 4 main floor plan sheet 5 upper floor plan sheet 6 sections sheet 7 details sheet 8 elections plans


Copyright 2025 Bennett Builden

BENNETT BUILDERS & REMODELERS



river, rocky 60 circle, **Service**

not for construction revised: 04/09/25



main floor electrical/mechanical schematic

electrical notes

The electrical plans shown here are suggested only! Electrical layouts can be altered as required for builder's standards, owner's preference or superceed by any governing code. The local governing codes take precedence over this layout.

All electrical work must be performed in accordance with all governing codes and regulations.

Provide proper electrical outlets for dishwasher, trash compactor, garbage disposal and microwave.

Provide proper electrical outlets for clothes dryer, range and air conditioners Provide proper outlet or wiring for whirlpool tub.

All smoke detectors are to be wired in series with battery back up power supply. Provide smoke alarms/detectors in compliance with all governing codes

All bathroom vents exhaust to the exterior of the dwelling.


Receptacle outlets in habitable rooms shall be installed so that no point measured horizontally along the floor line in any wall space is more than 6 feet from a receptable outlefliets that 12 foot spacing), a receptable shall be installed in each wall space 2 feet or more in writin.

Per nec 210.1 28 al 124-volt, ingingle phase 15 and 20 ampere branch circuits supplying outlets in dwelling unit family rooms, dring rooms, living rooms, partors, licrames, dens, tectoroms, surriors, receasion rooms, doests, hallways or similar rooms or areas shall be protected by a listed are-fault circuit interrupter, combination type, installed to provide protection of the hearth circuit.

The contractor shall verify that there is a complete system of grounding for all electrical equipment.

symbol legend





upper floor electrical/mechanical schematic

sheet 1 cover sheet sheet 2 elevations sheet 3 elevations sheet 4 main floor plan sheet 5 upper floor plan sheet 6 sections sheet 7 cetails sheet 8 elec-mech, plans





3 ediger

0376



front view

perspective views for design only



rear view



right side view



left side view





Bligger residence 3300 thomson circle, rocky river, ohio

approval
permit
not for construction
revised 04/09/25